

AD-A105 583

HOSKINS-WESTERN-SONDEREGGER INC LINCOLN NE

F/G 13/13

NATIONAL DAM SAFETY PROGRAM, WELSHMANS LAKE DAM (MO 31173), MIS--ETC(U)


OCT 80 R S DECKER, G JAMISON, G ULMER

DACW43-81-C-0003

NL

UNCLASSIFIED

1 OF 1  
AD-A105583



END  
DATE  
FILMED  
11-81  
DTIC

**LEVEL** *II*

**1**

**MISSISSIPPI-KASKASKIA-ST. LOUIS BASIN**

**AL A105583**

**WALSHMAN'S LAKE DAM**

**ST. FRANCOIS COUNTY, MISSOURI**

**NO. 105583**

**FIGURE 1. INSPECTION REPORT**

**WALSHMAN'S LAKE DAM, ST. FRANCOIS COUNTY, MISSOURI**

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER
	AD-A105583	
4. TITLE (and Subtitle) Phase I Dam Inspection Report National Dam Safety Program Welshmans Lake Dam (MO 31173) St. Francois County, Missouri	5. TYPE OF REPORT & PERIOD COVERED Final Report	6. PERFORMING ORG. REPORT NUMBER
7. AUTHOR(s) Hoskins-Western-Sonderegger, Inc.	8. CONTRACT OR GRANT NUMBER(s) DACW43-81-C-0003	9. PERFORMING ORGANIZATION NAME AND ADDRESS U.S. Army Engineer District, St. Louis Dam Inventory and Inspection Section, LMSED-PD 210 Tucker Blvd., North, St. Louis, Mo. 63101
10. CONTROLLING OFFICE NAME AND ADDRESS U.S. Army Engineer District, St. Louis Dam Inventory and Inspection Section, LMSED-PD 210 Tucker Blvd., North, St. Louis, Mo. 63101	11. REPORT DATE October 1980	12. NUMBER OF PAGES Approximately 70
13. MONITORING AGENCY NAME & ADDRESS (If different from Controlling Office) National Dam Safety Program. Welshmans Lake Dam (MO 31173), Mississippi - Kaskaskia - St. Louis Basin, <del>Mississippi</del> St. Francois County, Missouri. Phase I Inspection Report.	14. SECURITY CLASS. (of this report) UNCLASSIFIED	15. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report) (10) Rey S. /Decker Gordon /Jamison Garold /Ulmer Harold P. /Hoskins		
17. SUPPLEMENTARY N		
18. KEY WORDS (Continue on reverse side if necessary and identify by block number) Dam Safety, Lake, Dam Inspection, Private Dams		
19. ABSTRACT (Continue on reverse side if necessary and identify by block number) This report was prepared under the National Program of Inspection of Non-Federal Dams. This report assesses the general condition of the dam with respect to safety, based on available data and on visual inspection, to determine if the dam poses hazards to human life or property.		

DD FORM 1 JAN 73 1473

EDITION OF 1 NOV 65 IS OBSOLETE

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

## INSTRUCTIONS FOR PREPARATION OF REPORT DOCUMENTATION PAGE

**RESPONSIBILITY.** The controlling DoD office will be responsible for completion of the Report Documentation Page, DD Form 1473, in all technical reports prepared by or for DoD organizations.

**CLASSIFICATION.** Since this Report Documentation Page, DD Form 1473, is used in preparing announcements, bibliographies, and data banks, it should be unclassified if possible. If a classification is required, identify the classified items on the page by the appropriate symbol.

### COMPLETION GUIDE

**General.** Make Blocks 1, 4, 5, 6, 7, 11, 13, 15, and 16 agree with the corresponding information on the report cover. Leave Blocks 2 and 3 blank.

**Block 1.** Report Number. Enter the unique alphanumeric report number shown on the cover.

**Block 2.** Government Accession No. Leave Blank. This space is for use by the Defense Documentation Center.

**Block 3.** Recipient's Catalog Number. Leave blank. This space is for the use of the report recipient to assist in future retrieval of the document.

**Block 4.** Title and Subtitle. Enter the title in all capital letters exactly as it appears on the publication. Titles should be unclassified whenever possible. Write out the English equivalent for Greek letters and mathematical symbols in the title (see "Abstracting Scientific and Technical Reports of Defense-sponsored RDT/E," AD-667 000). If the report has a subtitle, this subtitle should follow the main title, be separated by a comma or semicolon if appropriate, and be initially capitalized. If a publication has a title in a foreign language, translate the title into English and follow the English translation with the title in the original language. Make every effort to simplify the title before publication.

**Block 5.** Type of Report and Period Covered. Indicate here whether report is interim, final, etc., and, if applicable, inclusive dates of period covered, such as the life of a contract covered in a final contractor report.

**Block 6.** Performing Organization Report Number. Only numbers other than the official report number shown in Block 1, such as series numbers for in-house reports or a contractor/grantee number assigned by him, will be placed in this space. If no such numbers are used, leave this space blank.

**Block 7.** Author(s). Include corresponding information from the report cover. Give the name(s) of the author(s) in conventional order (for example, John R. Doe or, if author prefers, J. Robert Doe). In addition, list the affiliation of an author if it differs from that of the performing organization.

**Block 8.** Contract or Grant Number(s). For a contractor or grantee report, enter the complete contract or grant number(s) under which the work reported was accomplished. Leave blank in in-house reports.

**Block 9.** Performing Organization Name and Address. For in-house reports enter the name and address, including office symbol, of the performing activity. For contractor or grantee reports enter the name and address of the contractor or grantee who prepared the report and identify the appropriate corporate division, school, laboratory, etc., of the author. List city, state, and ZIP Code.

**Block 10.** Program Element, Project, Task Area, and Work Unit Numbers. Enter here the number code from the applicable Department of Defense form, such as the DD Form 1498, "Research and Technology Work Unit Summary" or the DD Form 1634, "Research and Development Planning Summary," which identifies the program element, project, task area, and work unit or equivalent under which the work was authorized.

**Block 11.** Controlling Office Name and Address. Enter the full, official name and address, including office symbol, of the controlling office. (Equals to funding/sponsoring agency. For definition see DoD Directive 5200.20, "Distribution Statements on Technical Documents.")

**Block 12.** Report Date. Enter here the day, month, and year or month and year as shown on the cover.

**Block 13.** Number of Pages. Enter the total number of pages.

**Block 14.** Monitoring Agency Name and Address (if different from Controlling Office). For use when the controlling or funding office does not directly administer a project, contract, or grant, but delegates the administrative responsibility to another organization.

**Blocks 15 & 15a.** Security Classification of the Report: Declassification/Downgrading Schedule of the Report. Enter in 15 the highest classification of the report. If appropriate, enter in 15a the declassification/downgrading schedule of the report, using the abbreviations for declassification/downgrading schedules listed in paragraph 4-207 of DoD 5200.1-R.

**Block 16.** Distribution Statement of the Report. Insert here the applicable distribution statement of the report from DoD Directive 5200.20, "Distribution Statements on Technical Documents."

**Block 17.** Distribution Statement (of the abstract entered in Block 20, if different from the distribution statement of the report). Insert here the applicable distribution statement of the abstract from DoD Directive 5200.20, "Distribution Statements on Technical Documents."

**Block 18.** Supplementary Notes. Enter information not included elsewhere but useful, such as: Prepared in cooperation with . . . Translation of (or by) . . . Presented at conference of . . . To be published in . . .

**Block 19.** Key Words. Select terms or short phrases that identify the principal subjects covered in the report, and are sufficiently specific and precise to be used as index entries for cataloging, conforming to standard terminology. The DoD "Thesaurus of Engineering and Scientific Terms" (TEST), AD-672 000, can be helpful.

**Block 20.** Abstract. The abstract should be a brief (not to exceed 200 words) factual summary of the most significant information contained in the report. If possible, the abstract of a classified report should be unclassified and the abstract to an unclassified report should consist of publicly-releasable information. If the report contains a significant bibliography or literature survey, mention it here. For information on preparing abstracts see "Abstracting Scientific and Technical Reports of Defense-Sponsored RDT&E," AD-667 000.

WELSHMANS LAKE DAM  
ST. FRANCOIS COUNTY, MISSOURI  
MISSOURI INVENTORY NO. MO 31173

PHASE I INSPECTION REPORT  
NATIONAL DAM SAFETY PROGRAM

PREPARED BY  
HOSKINS-WESTERN-SONDEREGGER, INC.  
CONSULTING ENGINEERS  
LINCOLN, NEBRASKA

UNDER DIRECTION OF  
ST. LOUIS DISTRICT, CORPS OF ENGINEERS

FOR  
GOVERNOR OF MISSOURI

OCTOBER, 1980

Approved For	
NTI	<input checked="" type="checkbox"/>
DTIC	<input type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	
By	
Distribution/	
Availability Codes	
Dist	Special
A	

DTIC  
ELECT  
OCT 16 1981



REPLY TO  
ATTENTION OF

**DEPARTMENT OF THE ARMY**  
**ST. LOUIS DISTRICT, CORPS OF ENGINEERS**  
**210 TUCKER BOULEVARD, NORTH**  
**ST. LOUIS, MISSOURI 63101**

SUBJECT: Welshmans Lake Dam Phase I Inspection Report

This report presents the results of field inspection and evaluation of the Welshmans Lake Dam (MO 31173).

It was prepared under the National Program of Inspection of Non-Federal Dams.

This dam has been classified as unsafe, non-emergency by the St. Louis District as a result of the application of the following criteria:

- a. Spillway will not pass 50 percent of the Probable Maximum Flood without overtopping the dam.
- b. Overtopping of the dam could result in failure of the dam.
- c. Dam failure significantly increases the hazard to loss of life downstream.

SUBMITTED BY:

**SIGNED**

Chief, Engineering Division

**28 APR 1981**

Date

APPROVED BY:

**SIGNED**

Colonel, CE, District Engineer

**30 APR 1981**

Date

PHASE I INSPECTION REPORT  
NATIONAL DAM SAFETY PROGRAM

TABLE OF CONTENTS

<u>PARAGRAPH NO.</u>	<u>TITLE</u>	<u>PAGE NO.</u>
	Assessment Summary	
	Overview Photograph	
	SECTION 1 - PROJECT INFORMATION	
1.1	General	1
1.2	Description of Project	1
1.3	Pertinent Data	3
	SECTION 2 - ENGINEERING DATA	
2.1	Design	6
2.2	Construction	6
2.3	Operation	6
2.4	Evaluation	6
	SECTION 3 - VISUAL INSPECTION	
3.1	Findings	7
3.2	Evaluation	9
	SECTION 4 - OPERATIONAL PROCEDURES	
4.1	Procedures	10
4.2	Maintenance of Dam	10
4.3	Maintenance of Operating Facilities	10
4.4	Description of Any Warning System in Effect	10
4.5	Evaluation	10
	SECTION 5 - HYDRAULIC/HYDROLOGIC	
5.1	Evaluation of Features	11
	SECTION 6 - STRUCTURAL STABILITY	
6.1	Evaluation of Structural Stability	12
	SECTION 7 - ASSESSMENT/REMEDIAL MEASURES	
7.1	Dam Assessment	13
7.2	Remedial Measures	14

## APPENDIX A - MAPS

Plate A-1	Vicinity Topography
Plate A-2	Location Map
Plate A-3	Seismic Zone Map

## APPENDIX B - PHOTOGRAPHS

Plate B-1		Photo Index
Plate B-2	Photo No. 2	Overview from Right Upstream Bank
	Photo No. 3	Downstream Slope from Right End
Plate B-3	Photo No. 4	Crest of Dam from Right End
	Photo No. 5	Upstream Slope from Right End
Plate B-4	Photo No. 6	View Upstream through Spillway Channel
	Photo No. 7	View of Exit Channel which is normal to end of Spillway Slab
Plate B-5	Photo No. 8	View of Upstream Slope taken from entrance to Spillway Channel
	Photo No. 9	Looking upstream through the Spillway Channel
Plate B-6	Photo No. 10	Crest of Dam looking over the Spillway from the Left End
	Photo No. 11	View shows Woven Wire covering Upstream Slope (for Muskrat Control)
Plate B-7	Photo No. 12	Looking Upstream from near Center of Dam.
	Photo No. 13	Looking Downstream from near Center of Dam.
Plate B-8	Photo No. 14	Seep area near toe of Dam Downstream from Station 3+00
	Photo No. 15	Looking Upstream at Seep Area
Plate B-9	Photo No. 16	Seep Area Downstream from Station 2+50
	Photo No. 17	Thin-bedded Shaley Limestone Outcropping in Left Abutment Trough
Plate B-10	Photo No. 18	View showing undercutting of Downstream Lip of Spillway Apron
	Photo No. 19	Damage Area Downstream of the Dam
Plate B-11	Photo No. 20	Damage Area Downstream of the Dam

## APPENDIX C - PROJECT PLATES

Plate C-1	Phase I - Plan and Profile of Dam
Plate C-2	Phase I - Maximum Cross Section of Dam, Spillway Cross Sections and Centerline Profile

## APPENDIX D - HYDRAULIC AND HYDROLOGIC COMPUTATIONS

Plates D-1 and D-2	Hydrologic Computations
Plate D-3	Principal Spillway Rating Curve
Plate D-4	Elevation-Area Curve
Plate D-5	Ratio-Discharge Curves
Plates D-6 through D-28	Computer Input and Output for Ratios of PMF



APPENDIX E - GEOLOGY REPORT

Plate E-1

Engineering Geology Report by Missouri  
Geological Survey

PHASE I REPORT  
NATIONAL DAM SAFETY PROGRAM  
ASSESSMENT SUMMARY

Name of Dam	Welshmans Lake Dam
State Located	Missouri
County Located	St. Francois County
Stream	Tributary to Cabanne Course
Date of Inspection	October 29, 1980

Welshmans Lake Dam was inspected by an interdisciplinary team of engineers from Hoskins-Western-Sonderegger, Inc. The purpose of the inspection was to make an assessment of the general conditions of the dam with respect to safety, based upon available data and visual inspection, in order to determine if the dam poses hazards to human life or property.

The guidelines used in the assessment were furnished by the Department of the Army, Office of the Chief of Engineers and developed with the help of several Federal and State agencies, professional engineering organizations, and private engineers.

Welshmans Lake Dam has a height of thirty-two (32) feet and a storage capacity at the minimum top elevation of the dam of one-hundred-two (102) acre-feet. In accordance with the guidelines, a small size dam has a height greater than or equal to twenty-five (25) feet but less than forty (40) feet and a storage capacity greater than or equal to fifty (50) acre-feet but less than one thousand (1,000) acre-feet. The size classification is determined by either the storage capacity or height, whichever gives the larger size category. Welshmans Lake Dam is classified as a small size dam.

In accordance with the guidelines and based on visual observation, the dam is classified as having a high potential for damage and loss of life. Failure would threaten life and property. The estimated damage zone extends approximately two (2) miles downstream of the dam. Within the damage zone are several trailer houses, a barn, and 3 or 4 dwellings.

Our inspection and evaluation indicate that the spillway does not meet the minimum criteria set forth in the recommended guidelines for a small dam having a high hazard potential. In consideration of the small volume of water impounded and the size of the downstream floodplain 50 percent of the Probable Maximum Flood is the appropriate spillway design flood. The spillway will pass the 100-year flood (a flood having a 1 percent probability of being exceeded in any year) without overtopping the dam. The spillway will pass 35 percent of the Probable Maximum Flood without overtopping the dam. The Probable Maximum Flood (PMF) is defined as the flood that may be expected from the most severe combination of critical meteorologic and hydrologic conditions that are reasonably possible in the region.


Welshmans Lake Dam appears to be in excellent structural condition and the maintenance is very good.

Design data were not available for this dam. Based on the field inspection of the dam, the following remedial measure should be implemented by the owner on a high priority basis:


- (1) Increase the height of the dam and/or the spillway size to pass 50 percent of the probable maximum flood without overtopping the dam. In either case the spillway should be protected to prevent erosion.


The following operation and maintenance procedures are recommended and should be implemented by the owner in the near future:

- (1) Seepage and stability analyses comparable to the requirements of the recommended guidelines should be performed by an engineer experienced in the design and construction of dams.
- (2) The seepage at the toe of the dam should be monitored to determine changes in the amount or characteristics of effluent.
- (3) Measures should be taken to stabilize or minimize erosion under the concrete apron of the spillway.
- (4) Maintenance of this structure is generally very good and should be continued.
- (5) A program of regular inspection of the dam and spillway should be initiated, including seepage observations, and records of the inspections should be made a part of this project site.

  
Rey S. Decker  
E-3703

  
Gordon Jamison

  
Garold Ulmer  
E-19246

  
Harold P. Hoskins, Chairman of the Board  
Hoskins-Western-Sonderregger, Inc.  
E-8696




PHOTO NO. 1 - OVERVIEW

PHASE I INSPECTION REPORT  
NATIONAL DAM SAFETY PROGRAM  
WELSHMANS LAKE DAM - MO 31173  
ST. FRANCOIS COUNTY, MISSOURI

SECTION 1 - PROJECT INFORMATION

1.1 GENERAL

- a. Authority. The National Dam Inspection Act, Public Law 92-367, authorized the Secretary of the Army through the Corps of Engineers, to initiate a program of safety inspection of dams throughout the United States. Pursuant to the above, the St. Louis District, Corps of Engineers, District Engineer directed that a safety inspection of Welshmans Lake Dam be made.
- b. Purpose of Inspection. The purpose of the inspection was to make an assessment of the general condition of the dam with respect to safety, based upon available data and visual inspection, in order to determine if the dam poses hazards to human life or property.
- c. Evaluation Criteria. Criteria used to evaluate the dam were furnished by the Department of the Army, Office of the Chief of Engineers, in "Recommended Guidelines for Safety Inspection of Dams", Appendix D to "Report of the Chief of Engineers on the National Program of Inspection of Dams", dated May, 1975, and published by the Department of the Army, Office of the Chief of Engineers.

1.2 DESCRIPTION OF PROJECT

- a. Description of Dam and Appurtenances.
  - (1) Embankment. This dam is a small earth fill structure approximately 440 feet in length and 32 feet in height. The maximum water storage at the minimum top of dam elevation is 102 acre-feet.
  - (2) Principal Spillway. The uncontrolled principal (and only) spillway is excavated through the left abutment. Approximately 37 feet of the channel is paved with a trapezoidal shaped concrete slab that culminates at the edge of the downstream exit channel with a 30 foot  $\pm$  length concrete sill. Flows over the sill enter the downstream channel approximately normal to the centerline of the exit channel. The exit channel is cut into shale and siltstone.
  - (3) Low-Level Outlet. There is no operating low-level outlet. A six-inch pipe was installed at the time of construction but has since been plugged with concrete and is no longer operative.

(4) Pertinent physical data are given in paragraph 1.3.

- b. Location. The dam is located in the northwest part of St. Francois County as shown on Plate A-2. The dam is about one mile southwest of the City of Bonne Terre and is shown on Plate A-1 in the SW 1/4 of Section 15, T37N, R4E. The lake formed behind the dam is in the same quarter section.
- c. Size Classification. Criteria for determining the size classification of dams and impoundments are presented in the guidelines referenced in paragraph 1.1c above. Welshmans Lake Dam has a height of 32 feet and a storage capacity of 102 acre-feet. This dam is classified as a small size dam. A small size dam has a height greater than or equal to 25 feet but less than 40 feet and a storage capacity greater than or equal to 50 acre-feet but less than 1,000 acre-feet. The size classification is determined by either the storage or height, whichever gives the larger size category.
- d. Hazard Classification. Guidelines for determining hazard classification of dams and impoundments are presented in the guidelines as referenced in paragraph 1.1c above.

Aerial photographs of the downstream damage zone of this dam were taken in October, 1980. These photographs were used as reference in the field observations of the damage zone which were made during the inspection. Based on the field observations and on the referenced guidelines this dam is in the High Hazard Potential Classification. The estimated damage zone extends approximately two miles downstream of the dam. Within the damage zone are several trailer houses, a barn, and 3-4 dwellings. Photos 19 and 20 show some of the damage area.

- e. Ownership. The dam is owned by Mr. Paul Williams, President, U.S. Tool Grinding, Inc., 34 Birch Street, Desloge, Missouri 63601.
- f. Purpose of Dam. Recreation.
- g. Design and Construction History. No plans were found for the dam. Mr. Williams said the dam was built in 1973 and that the Missouri State Conservation Department helped in the development. A geologic report prepared by the Missouri Geological Survey is included with this report in Appendix E. Mr. Williams reported that a core trench was excavated to a depth of about 10 feet and was bottomed in shale. Most of the material for the embankment came from the top of the hill on the left abutment.
- h. Normal Operating Procedure. There are no operating facilities for this dam. The pool level is controlled by rainfall, infiltration, evaporation, and the capacity of the uncontrolled spillway. Mr. Williams reported that the maximum flow through the spillway was 1 to 1.5 feet. The dam has never been overtopped.

### 1.3 PERTINENT DATA

- a. Drainage Area. 143.9 acres (0.225 square miles).
- b. Discharge at Damsite.
  - (1) All discharges at the damsite are through the uncontrolled principal spillway excavated through the left abutment.
  - (2) Estimated maximum flood at damsite -- Mr. Williams reported that the maximum depth of flow through the spillway was approximately 18 inches.
  - (3) The principal spillway capacity varies from 0 c.f.s. at elevation 819.4 feet to 467 c.f.s. at the minimum top of dam (elevation 823.9 feet).
  - (4) Total spillway capacity at the minimum top of dam is 467 c.f.s.±.
- c. Elevations (feet above M.S.L.).
  - (1) Observed pool - 816
  - (2) Normal pool - 819.4
  - (3) Spillway crest - 819.4
  - (4) Maximum experienced pool - 821±
  - (5) Top of dam (minimum) - 823.9
  - (6) Streambed - 792 ±
  - (7) Maximum Tailwater - Unknown
- d. Reservoir. Length (feet) of pool.
  - (1) At spillway crest - 1100
  - (2) At top of dam (minimum) - 1400
- e. Storage (Acre-feet).
  - (1) Observed pool - 45±
  - (2) Normal pool - 65±
  - (3) Spillway crest - 65±
  - (4) Maximum experienced pool - 80±

(5) Top of dam (minimum) - 102

f. Reservoir Surface (Acres).

(1) Observed pool - 5.5 ±

(2) Normal pool - 7.1 ±

(3) Spillway crest - 7.1 ±

(4) Maximum experienced pool - 7.8 ±

(5) Top of dam (minimum) - 9.1 ±

g. Dam.

(1) Type - Earth fill

(2) Length - 440 ft

(3) Height - 32 ft

(4) Top Width - 16 ft average (varies from 15 to 18 feet)

(5) Side slopes.

(a) Downstream - 1V on 2.4H ±

(b) Upstream - 1V on 2.8H ± (to water edge)

(6) Zoning - None

(7) Impervious core - Unknown

(8) Cutoff - 10 feet deep into shale (reported by owner)

(9) Grout curtain - None

(10) Wave protection - Vegetation

(11) Drains - None

h. Diversion Channel and Regulating Tunnel. - None

i. Spillway.

(1) Principal (and only)

(a) Type - Uncontrolled channel excavated through the left abutment.



- (b) Control section - Concrete slab sill approximately 30 ft long
- (c) Crest elevation - 819.4 ft
- (d) Upstream channel - To shale and limestone bedrock, approximately flat slope and 100 ft in length
- (e) Downstream channel - Cut into shale running normal to concrete sill section.  $8.7 \pm \%$  grade

j. Regulating Outlets. - None

## SECTION 2 - ENGINEERING DATA

### 2.1 DESIGN

No design data were available for this dam. The Missouri Geological Survey made an investigation of the site in 1969. A copy of this report is included in Appendix E.

### 2.2 CONSTRUCTION

No construction records were available. Mr. Williams reported that the dam was built in 1973 and that the core trench was about 10 feet deep and was blasted into shale.

### 2.3 OPERATION

There are no operating procedures for this dam.

### 2.4 EVALUATION

- a. Availability. No design data were available.
- b. Adequacy. The field surveys and visual observations presented herein are considered adequate to support the conclusions of this report. Seepage and stability analyses comparable to the requirements of the "Recommended Guidelines for Safety Inspection of Dams" were not available, which is considered a deficiency. These seepage and stability analyses should be performed for appropriate loading conditions (including earthquake loads) and made a matter of record.
- c. Validity. Not applicable.

## SECTION 3 - VISUAL INSPECTION

### 3.1 FINDINGS

- a. General. A visual inspection of the Welshmans Lake Dam was made on October 29, 1980. Engineers from Hoskins-Western-Sonderegger, Inc., Lincoln, Nebraska, making the inspection were:

Rey S. Decker - Geotechnical  
Garold G. Ulmer - Hydraulics and Hydrology  
Gordon Jamison - Hydraulics and Hydrology

The owner, Mr. Paul Williams, and the caretaker, Mr. Richard Hickman, were present during the inspection.

- b. Dam.

- (1) Geology and Soils (abutment and embankment). This dam is situated in the Ozark Physiographic Province. Its upland setting is topographically characteristic of the province exhibiting moderate slopes, youthful valleys, a thin to absent loess mantle and exposures of the Upper Cambrian bedrock formations. The structural setting is typical of the Ozark Uplift. Multiple faults comprising the Big River, Simons Mountain and Cabanne Systems surround the area. Seismic activity is moderate; however, the recorded intensities are low.

The bedrock formation is the Derby-Doerun formation of the Elvins Group of the Upper Cambrian and consists of alternating beds of thinly-bedded arkosic limestones, shales and medium-bedded dolomites. Solution cavitation and fracture porosity is not evident in the bedrock exposures. Thin-bedded silty shales and limestones are exposed in the left abutment trough and in the exit channel of the spillway. Seepage at the shale-limestone contact at the left abutment base and in the shales in the valley bottom exhibited flows of less than 0.5 gpm at the dam site and less than 5 gpm in the channel downstream of the dam. Materials in the narrow valley section consist of 5 to 10 feet of CL-ML alluvium-colluvium overlying shale. Materials in the embankment consist of CL-CH soils borrowed principally from a gently sloping glade area above the left abutment. Numerous earthquakes ranging in Modified Mercalli intensity from II to V are recorded by Stover, Reagor and Algermission, 1979. These include dates in 1884, 1907, 1929, 1946, 1966, 1969, 1970 and 1973. All occurred at a radial distance of less than 30 miles from the dam site. The entire watershed is owned by Mr. Williams and is maintained as a primitive area.

- (2) Upstream Slope. The upstream slope is covered with a good vegetative cover of fescue and crown vetch. It has a woven

wire cover for muskrat control that extends from normal pool level about 5 feet up the slope. Photo No. 11 shows the woven wire. There is some slight erosion at the normal pool elevation. No cracks, slumps, or other deformations were observed. No rodent activity was observed. Photos 5 and 11 show the upstream slope.

- (3) Crest. Field measurements indicate the crest elevation varies approximately 18 inches. The crest width varies from 15 feet to 18 feet. The crest has a good vegetative cover. There was no evidence of cracks or deformations. Photos No. 3, 4, and 10 show the crest.
- (4) Downstream Slope. The downstream slope has an excellent cover of fescue and crown vetch. The downstream slope is approximately 1V to 2.4H, with no evidence of cracks, slides, or rodent activity. Photo 3 shows the downstream slope. There are signs of seepage near the toe of the slope downstream from about Sta. 3+00. Borings about 25 feet up the slope from the seepage outcrop indicate water at about 2' (could be the phreatic surface). Materials in the borings were CL or CH and erosion resistant. Seepage from this area was discharging at less than 0.5 gal/min. Photos 14 and 15 show this seep area. Mr. Williams reported that a 6-inch diameter drawdown pipe with valve was installed through the base of the dam. Some leakage developed along this pipe, and it had been plugged by pumping it full of concrete. (This recent work accounts for the disturbed surface shown in the photos).

Another seep area was observed at the toe of the slope downstream from Sta. 2+50 in the left abutment trough. This area was dry at the time of inspection but supported a good growth of cattails. It would appear that this seepage comes through the thinly bedded siltstone and shaley limestone in the left abutment. Photo No. 16 shows the seep area, and Photo No. 17 shows the shaley limestone outcrop at the toe of the left abutment trough, just up the slope from the seep area.

c. Appurtenant Structures.

- (1) Principal Spillway. The spillway channel is excavated in the left abutment. The floor of the entrance channel is shaley limestone and is capped with a control of concrete about 30 ft long. The inside banks of the inlet channel are covered with indurated sandstone riprap. The exit channel is normal to the downstream apron and is cut into shale and limestone. Photos No. 6, 7, 9, 10 and 18 show views of the spillway.

The outflow apron of the concrete sill is undercutting. It appears that the apron has been extended to correct this problem, but erosion is still active under the apron. Photo No. 18 shows the undercutting of the apron.

- (2) Low-Level Outlet. The 6-inch diameter pipe which was installed at the time of construction has been plugged with concrete and is no longer operative.
- d. Reservoir Area. There is no significant erosion around the shoreline. The shoreline appears to be clear of trees, brush, and trash. The reservoir elevation was 816 ft (3.4 ft below the crest of the spillway) at the time of inspection. There was no evidence of abnormal siltation in the reservoir. Photos No. 2 and 12 show portions of the reservoir.
- e. Downstream Channel. The downstream channel is cut to bedrock and is overgrown with a natural growth of trees and brush.

### 3.2 EVALUATION

Based on visual inspection and measurements, the dam appears to be in excellent structural condition with no likely potential of failure. Materials in the dam appear to be highly resistant to erosion and piping, and the present seepage at the toe of the dam should not endanger the stability of the structure. Erosion in the spillway channel does not endanger the dam nor should it lead to any sudden breach of the reservoir.

## SECTION 4 - OPERATIONAL PROCEDURES

### 4.1 PROCEDURES

There are no controlled outlet works for this dam. The pool level is controlled by rainfall, infiltration, evaporation, and the capacity of the uncontrolled spillways.

### 4.2 MAINTENANCE OF DAM

Maintenance of the dam appears to be excellent. The crown vetch cover minimizes maintenance. The caretaker, Mr. Hickman, lives near the right end of the dam and is available for on-the-spot repairs. Some additional measures should be taken to stabilize the downstream apron of the spillway sill. Mr. Hickman traps out the muskrats and/or beavers as they occur.

### 4.3 MAINTENANCE OF OPERATING FACILITIES

No operating facilities exist at this dam.

### 4.4 DESCRIPTION OF ANY WARNING SYSTEM IN EFFECT

There is no warning system in effect for this dam.

### 4.5 EVALUATION

The excellent condition of this dam is in great part due to the pride of the owner and the availability and resourcefulness of the caretaker.

## SECTION 5 - HYDRAULIC/HYDROLOGIC

### 5.1 EVALUATION OF FEATURES

- a. Design Data. No design data were found for this dam.
- b. Experience Data. The drainage area, reservoir surface area, and elevation-storage data were developed from the USGS Bonne Terre, Missouri 7-1/2 minute topographic quadrangle map. The hydraulic computations for the spillway and dam overtopping discharge ratings were based on data collected in the field at the time of the field inspection. Hydrologic computations are included in this report as Appendix D.
- c. Visual Observations.
  - (1) The principal spillway is in good condition with minor undercutting of the downstream apron.
  - (2) The crest as well as both slopes are in excellent condition.
- d. Overtopping Potential. The spillway is too small to pass 50 percent of the probable maximum flood without overtopping. The spillway will pass 35% of the probable maximum flood and the 1% probability flood without overtopping. Overtopping of a dam should always be avoided. Overtopping would be dangerous because the flow of the water over the crest could erode the downstream face of the dam and, if continued long enough, could breach the dam with sudden release of all of the impounded water onto the downstream flood plain.

The results of the routings through the dam are tabulated in regards to the following conditions:

Frequency	Inflow Discharge c.f.s.	Outflow Discharge c.f.s.	Maximum Pool Elevation	*Maximum Depth Over Dam Feet	Duration Over Top Hours
1%	650	220	822.3	-	-
1/2 PMF	1360	835	824.9	1.0	1-
PMF	2720	2540	826.1	2.2	3+
0.35 PMF	960	470	823.9	-	-

\* Minimum top of dam elevation - 823.9

According to the recommended guidelines from the Department of the Army, Office of the Chief of Engineers, this dam is classified as having a high hazard potential rating and a small size. Therefore, the 1/2 PMF to PMF is the test for the adequacy of the dam and its spillway.

The estimated damage zone is described in paragraph 1.2d in this report.

## SECTION 6 - STRUCTURAL STABILITY

### 6.1 EVALUATION OF STRUCTURAL STABILITY

- a. Visual Observation. Based on visual observation and measurements this dam appears to be in excellent condition and structurally stable. There was no evidence of slumps, cracks, slides or abnormal deformations that would indicate structural stress. The nature of the materials in the embankment and the downstream slope of 1V on 2.4H should provide adequate safety against shear failures. The effects of seepage on the stability of the dam are unknown although no detrimental effects were observed during the inspection.
- b. Design and Construction Data. No design or construction data were available. Seepage and stability analyses comparable to the requirements of the "Recommended Guidelines for Safety Inspection of Dams" were not available, which is considered a deficiency.
- c. Operating Records. There are no controlled operating facilities for this dam.
- d. Post Construction Changes. Mr. Williams reported that the 6-inch drawdown pipe was pumped full of concrete to correct some seepage or leakage problems that developed after the dam was completed.
- e. Seismic Stability. This dam is located in Seismic Zone 2 as shown on Plate A-3. An earthquake of the magnitude predicted in this area could cause minor structural damage to this dam.



## SECTION 7 - ASSESSMENT/REMEDIAL MEASURES

### 7.1 DAM ASSESSMENT

- a. Safety. Based on visual observations and the measurements made during the inspection, this dam appears to be in excellent condition and structurally stable. The approximate hydrologic analysis performed for this report indicates that the spillway is too small to pass 50 percent of the probable maximum flood without overtopping the dam. The spillway will pass the 1 percent probability flood as well as 35 percent of the probable maximum flood without overtopping. The 50 percent probable maximum flood will overtop the lowest point on the crest of the dam by one foot for a period of one hour. The erosional damage to the dam caused by such overtopping is not known.

The erosion and undercutting under the concrete spillway apron is not serious at the present time but could lead to deterioration of the concrete control section if not corrected.

Seepage along the toe of the dam does not appear, at the present time, to endanger the stability of the dam. It would be well, however, to monitor the seep areas for changes in volume and characteristics. Seepage and stability analyses comparable to the requirements of the "Recommended Guidelines for Safety Inspection of Dams" were not available, which is considered a deficiency.

- b. Adequacy of Information. The measurements and observations made during the inspection are considered adequate to support the conclusions set forth in this report. Seepage and stability analyses comparable to the requirements of the "Recommended Guidelines for Safety Inspection of Dams" were not available, which is considered a deficiency.
- c. Urgency. The remedial measures recommended in paragraph 7.2b should be accomplished in the near future. The item recommended in paragraph 7.2a. should be pursued on a high priority basis.
- d. Necessity for Further Investigations. The seepage and stability analyses recommended in paragraph 7.2b should be accomplished by the owner in the near future.
- e. Seismic Stability. This dam is located in Seismic Zone 2 as shown on Plate A-3. An earthquake of this magnitude is expected to cause some minor damage to this dam. It is recommended that the prescribed seismic loading for Seismic Zone 2 be applied in any stability analyses performed for this dam.

## 7.2 REMEDIAL MEASURES

The following remedial measures and maintenance procedures are recommended. All remedial measures should be performed under the guidance of a registered professional engineer experienced in the design and construction of earth dams.


### a. Alternatives.

- (1) Increase the height of the dam and/or the spillway size to pass 50 percent of the probable maximum flood without overtopping the dam. In either case the spillway should be protected to prevent erosion.

### b. Operation and Maintenance Procedures.

- (1) Seepage and stability analyses comparable to the requirements of the recommended guidelines should be performed by an engineer experienced in the design and construction of dams.
- (2) The seepage at the toe of the dam should be monitored to determine changes in the amount or characteristics of effluent.
- (3) Measures should be taken to stabilize or minimize erosion under the concrete apron of the spillway.
- (4) Maintenance of this structure is generally very good and should be continued.
- (5) A program of regular inspection of the dam and spillway should be initiated, including seepage observations, and records of the inspections should be made a part of this project file.

APPENDIX A  
MAPS



Scale in feet  
2000 1000 0 2000 4000

Contour Interval - 20'




# VICINITY TOPOGRAPHY

WELSHMANS LAKE DAM  
ST. FRANCOIS COUNTY, MISSOURI  
MO 31173


PLATE A-1





MISSOURI  
SEISMIC ZONE MAP

APPENDIX B  
PHOTOGRAPHS



WELSHMAN'S LAKE DAM  
ST. FRANCOIS COUNTY, MISSOURI  
MO. 31173

PHOTO INDEX

PLATE B-1





PHOTO NO. 2 - OVERVIEW FROM RIGHT UPSTREAM BANK



PHOTO NO. 3 - DOWNSTREAM SLOPE FROM RIGHT END



PHOTO 4 - CREST OF DAM FROM RIGHT END



PHOTO 5 - UPSTREAM SLOPE FROM RIGHT END

NOV 1

FROM 2



PHOTO NO. 6 - VIEW LOOKING UPSTREAM THROUGH THE SPILLWAY CHANNEL



PHOTO NO. 7 - VIEW OF EXIT CHANNEL WHICH IS NORMAL TO END OF SPILLWAY SLAB

C



PHOTO 8 - VIEW OF UPSTREAM SLOPE TAKEN FROM ENTRANCE TO SPILLWAY CHANNEL



PHOTO 9 - LOOKING DOWNSTREAM THROUGH THE SPILLWAY CHANNEL




PHOTO NO. 10 - CREST OF DAM LOOKING OVER THE SPILLWAY FROM  
THE LEFT END




PHOTO NO. 11 - VIEW SHOWS THE WOVEN WIRE COVERING THE UPSTREAM  
SLOPE (FOR MUSKRAT CONTROL)



PHOTO NO. 12 - LOOKING UPSTREAM FROM NEAR CENTER OF DAM



PHOTO NO. 13 - LOOKING DOWNSTREAM FROM NEAR CENTER OF DAM



PHOTO NO. 14 - SEEP AREA NEAR TOE OF DAM DOWNSTREAM FROM  
STATION 3+00




PHOTO NO. 15 - LOOKING UPSTREAM AT SEEP AREA

C



PHOTO NO. 16 - SEEP AREA DOWNSTREAM FROM STATION 2+50




PHOTO NO. 17 - THIN BEDDED SHALEY LIMESTONE OUTCROPPING IN THE TOE OF THE LEFT ABUTMENT TROUGH





PHOTO NO. 18 - VIEW SHOWING UNDERCUTTING OF THE DOWNSTREAM  
LIP OF THE SPILLWAY APRON



PHOTO NO. 19 - DAMAGE AREA DOWNSTREAM FROM DAM




PHOTO NO. 20 - DAMAGE AREA DOWNSTREAM FROM DAM

APPENDIX C  
PROJECT PLATES






PLAN OF DAM  
Scale: 1"=100'



CENTERLINE PROFILE OF DAM  
Scale As Shown

# WELSHMAN'S LAKE DAM MO. ID NO. 31173




APPENDIX D  
HYDRAULIC AND HYDROLOGIC DATA


## HYDROLOGIC COMPUTATION


1. The SCS dimensionless unit hydrograph and the systemized computer program HEC-1 (Dam Safety Version), July 1978, prepared by the Hydrologic Engineering Center, U.S. Corps of Engineers, Davis, California, were used to develop the inflow hydrographs (See this Section).
  - a. Twenty-four hour, one percent probabilistic rainfall for the dam location was taken from the data for the rainfall station at Sullivan, MO. as supplied by the St. Louis District, Corps of Engineers per their letter dated 6 March 1979. The twenty-four hour probable maximum precipitation was taken from the curves of Hydrometeorological Report No. 33 and current Corps of Engineers and St. Louis policy and guidance for hydraulics and hydrology.
  - b. Drainage area = 0.225 square miles (143.9 acres).
  - c. Time of concentration of runoff = 14 minutes (computed from the "Kirpich" formula and the California Department of Highways Culvert Practice formula).
  - d. The antecedent storm conditions for the probable maximum precipitation were heavy rainfall and low temperatures which occurred on the previous 5 days (SCS AMC III). The antecedent storm conditions for the one percent probabilistic precipitation were an average of the conditions which have preceded the occurrence of the maximum annual flood on numerous watersheds (SCS AMC II). The initial pool elevation was assumed at the crest of the principal spillway.
  - e. The total twenty-four hour storm duration losses for the one percent probabilistic storm were 2.66 inches. The total losses for the PMF storm were 1.44 inches. These data are based on SCS runoff curve No. 77 and No. 89 for antecedent moisture conditions SCS AMC II and AMC III respectively. The watershed is composed primarily of SCS soil groups. C & D (Pevidge-Cantwell-Gasconade soils). The watershed is 100% wooded.
  - f. Average soil loss rates = 0.05 inch per hour approximately (For PMF storm, AMC III).
2. The combined discharge rating consisted of two components: the flow through the spillway and the flow going over the top of the dam.
  - a. The spillway rating curve was developed using the Corps of Engineers, Water Surface Profile HEC-2 computer program. Critical depth was assumed at the downstream end of the concrete control.
  - b. The flows over the dam were determined by using the dam overtopping analyses (irregular top of dam) within the HEC-1 (Dam Safety Version) program.

3. Floods were routed through the reservoir using the HEC-1 (Dam Safety Version) program to determine the capabilities of the spillway and dam embankment crest. The input, output and plotted hydrographs are attached in this Section.









A1		WELSHMANS LAKE DAM / MU. ID. NO 31173	
A2		SAFETY ANALYSIS OF DAM OVERTOPPING USING ASSIGNED FLOOD FREQUENCIES	
A3		H & H ANALYSIS BY ROUTING PMF RATIOS THRU THE RESERVOIR	
B-	288000000000000005		00000000000000000003
B1	5		
J	100000008000000001		
J1	.0500000.1400000.1500000.2000000.2500000.3500000.50000001.0		
K	000000001		000000000000000000001
K1	CALCULATION OF INFLOW HYDRO TO WELSHMANS LAKE		
M	100000020000.22500000000000.2250000001.000000000000000000000001		
P	0000026.1000001020000012100000130		
T		-1.0	-89.0
W2	00000.17		
X	0		
X	-.0100000001		
K	100000002		000000020000000000000001
K1	ROUTED FLOWS THRU WELSHMANS LAKE DAM		
Y	00000001000000001		
Y1	1	-819.4	-1
Y4	819.40000820.0000820.6000821.2000822.1000822.3000823.5000824.1000824.5000825.3		
Y4	826.1000826.8000827.1		
Y5	00000002000000050000000100000000200000000300000000400000000500000000600000000800		
Y5	100000001200000001300		
\$A	0.000000.5000001.6000003.2000005.3000007.4000009.6000012.0000015.1		
\$E	794.0000800.0000805.0000810.0000815.0000820.0000825.0000830.0000835.0		
\$S	819.4		
\$D	823.9000002.8000001.5000000420		
\$L	00000002700000070000000120000000170000000200000000250000000405000000420000000445		
\$V	823.9000824.0000824.7000824.9000824.9000824.9000825.3000825.6000825.7000827.0		

99

\*\*\*\*\*  
 FLOOD HYDROGRAPH PACKAGE (HEC-1)  
 DAM SAFETY VERSION JULY 1978  
 LAST MODIFICATION 26 FEB 79  
 \*\*\*\*\*

RUN DATE 08/11/07.  
 TIME 10.40.04.

WELSHMANS LAKE DAM / MD. ID. NO 31173  
 SAFETY ANALYSIS OF DAM OVERTOPPING USING ASSIGNED FLOOD FREQUENCIES  
 II & H ANALYSIS BY ROUTING PMF RATIOS THRU THE RESERVOIR

JOB SPECIFICATION									
NO	NHR	NMIN	IDAY	IHR	IMIN	METPC	IPLT	IPRT	NSTAN
28A	0	5	0	0	0	0	0	3	0
JOPER				NWT	LROPT	TRACE			
5				0	0	0			

MULTI-PLAN ANALYSES TO BE PERFORMED

RTIOSE = .05 .10 .15 .20 .25 .35 .50 1.00  
 NPLAN= 1 NRTIO= 8 LRTIO= 1

\*\*\*\*\*

SUB-AREA RUNOFF COMPUTATION

CALCULATION OF INFLOW HYDRO TO WELSHMANS LAKE

ISTAO	ICOMP	IECON	ITAPE	JPLT	JPRI	INAME	ISTAGE	IAUTO
000001	0	0	0	0	0	1	0	0

HYDROGRAPH DATA									
IHYDG	IUNG	TAREA	SNAP	TRSDA	TRSPC	RATIO	ISNOW	ISAME	LOCAL
1	2	23	0.00	23	1.00	0.000	0	1	0

PRECIP DATA  
 SPFE PMS R6 R12 R24 R48 R72 R96  
 0.00 26.10 102.00 121.00 130.00 0.00 0.00 0.00

LOSS DATA  
 LROPT STKR DLTKR RTIOL ERAIN STRKS RTIOK STRTL CNSTL ALSMX RTIMP  
 0 0.00 0.00 1.00 0.00 0.00 1.00 -1.00 -89.00 0.00 0.00

CURVE NO = -69.00 WETNESS = -1.00 EFFECT CN = 89.00

UNIT-HYDROGRAPH DATA  
 TC= 0.00 LAG= .17

RECESSION DATA  
 SINTO= 0.00 ORCSN= -.01 RTIOE= 1.00

UNIT-HYDROGRAPH-12-END-OF PERIOD ORIGINATES. TC= 0.00 HOURS, LAG= .17 VOL= 1.00  
 156. 472. 485. 304. 153. 82. 43. 23. 12. 6.

END-OF-PERIOD FLOW

MO.DA	HR.MN	PERIOD	RAIN	EXCS	LOSS	COMP O	MO.DA	HR.MN	PERIOD	RAIN	EXCS	LOSS	COMP O
1.01	.05	1	.01	0.00	.01	0.	1.01	12.05	145	.22	.21	.01	139.
1.01	.10	2	.01	0.00	.01	0.	1.01	12.10	146	.22	.22	.01	209.
1.01	.15	3	.01	0.00	.01	0.	1.01	12.15	147	.22	.22	.01	282.
1.01	.20	4	.01	0.00	.01	0.	1.01	12.20	148	.22	.22	.01	327.
1.01	.25	5	.01	0.00	.01	0.	1.01	12.25	149	.22	.22	.01	350.
1.01	.30	6	.01	0.00	.01	0.	1.01	12.30	150	.22	.22	.01	363.
1.01	.35	7	.01	0.00	.01	0.	1.01	12.35	151	.22	.22	.00	370.
1.01	.40	8	.01	0.00	.01	0.	1.01	12.40	152	.22	.22	.00	374.
1.01	.45	9	.01	0.00	.01	0.	1.01	12.45	153	.22	.22	.00	376.
1.01	.50	10	.01	0.00	.01	0.	1.01	12.50	154	.22	.22	.00	377.
1.01	.55	11	.01	0.00	.01	0.	1.01	12.55	155	.22	.22	.00	378.
1.01	1.00	12	.01	0.00	.01	0.	1.01	13.00	156	.22	.22	.00	379.
1.01	1.05	13	.01	0.00	.01	0.	1.01	13.05	157	.27	.26	.00	386.
1.01	1.10	14	.01	0.00	.01	0.	1.01	13.10	158	.27	.26	.00	407.
1.01	1.15	15	.01	0.00	.01	0.	1.01	13.15	159	.27	.26	.00	429.
1.01	1.20	16	.01	0.00	.01	0.	1.01	13.20	160	.27	.26	.00	442.
1.01	1.25	17	.01	0.00	.01	0.	1.01	13.25	161	.27	.26	.00	449.
1.01	1.30	18	.01	0.00	.01	0.	1.01	13.30	162	.27	.26	.00	453.
1.01	1.35	19	.01	0.00	.01	0.	1.01	13.35	163	.27	.26	.00	455.
1.01	1.40	20	.01	0.00	.01	0.	1.01	13.40	164	.27	.26	.00	457.
1.01	1.45	21	.01	0.00	.01	0.	1.01	13.45	165	.27	.26	.00	457.
1.01	1.50	22	.01	0.00	.01	0.	1.01	13.50	166	.27	.26	.00	458.
1.01	1.55	23	.01	0.00	.01	1.	1.01	13.55	167	.27	.26	.00	458.
1.01	2.00	24	.01	0.00	.01	1.	1.01	14.00	168	.27	.26	.00	459.
1.01	2.05	25	.01	0.00	.01	2.	1.01	14.05	169	.33	.33	.00	469.
1.01	2.10	26	.01	0.00	.01	2.	1.01	14.10	170	.33	.33	.00	501.
1.01	2.15	27	.01	0.00	.01	2.	1.01	14.15	171	.33	.33	.00	533.
1.01	2.20	28	.01	0.00	.01	3.	1.01	14.20	172	.33	.33	.00	553.
1.01	2.25	29	.01	0.00	.01	3.	1.01	14.25	173	.33	.33	.00	563.
1.01	2.30	30	.01	0.00	.01	3.	1.01	14.30	174	.33	.33	.00	569.
1.01	2.35	31	.01	0.00	.01	4.	1.01	14.35	175	.33	.33	.00	572.
1.01	2.40	32	.01	0.00	.01	4.	1.01	14.40	176	.33	.33	.00	574.
1.01	2.45	33	.01	0.00	.01	5.	1.01	14.45	177	.33	.33	.00	575.
1.01	2.50	34	.01	0.00	.01	5.	1.01	14.50	178	.33	.33	.00	575.
1.01	2.55	35	.01	0.00	.01	5.	1.01	14.55	179	.33	.33	.00	576.
1.01	3.00	36	.01	0.00	.01	6.	1.01	15.00	180	.33	.33	.00	576.
1.01	3.05	37	.01	0.00	.01	6.	1.01	15.05	181	.20	.20	.00	556.
1.01	3.10	38	.01	0.00	.01	6.	1.01	15.10	182	.40	.40	.00	526.
1.01	3.15	39	.01	0.00	.01	6.	1.01	15.15	183	.40	.40	.00	558.
1.01	3.20	40	.01	0.00	.01	7.	1.01	15.20	184	.61	.60	.00	648.
1.01	3.25	41	.01	0.00	.01	7.	1.01	15.25	185	.71	.71	.00	801.
1.01	3.30	42	.01	0.00	.01	7.	1.01	15.30	186	1.72	1.71	.01	1123.
1.01	3.35	43	.01	0.00	.01	8.	1.01	15.35	187	2.83	2.82	.01	1894.
1.01	3.40	44	.01	0.00	.01	8.	1.01	15.40	188	1.11	1.11	.00	2708.
1.01	3.45	45	.01	0.00	.01	8.	1.01	15.45	189	.71	.71	.00	2716.
1.01	3.50	46	.01	0.01	.01	8.	1.01	15.50	190	.61	.61	.00	2188.
1.01	3.55	47	.01	0.01	.01	9.	1.01	15.55	191	.40	.40	.00	1653.
1.01	4.00	48	.01	0.01	.01	9.	1.01	16.00	192	.40	.40	.00	1264.
1.01	4.05	49	.01	0.01	.01	9.	1.01	16.05	193	.31	.31	.00	993.
1.01	4.10	50	.01	0.01	.01	9.	1.01	16.10	194	.31	.31	.00	603.
1.01	4.15	51	.01	0.01	.01	9.	1.01	16.15	195	.31	.31	.00	683.
1.01	4.20	52	.01	0.01	.01	10.	1.01	16.20	196	.31	.31	.00	615.
1.01	4.25	53	.01	0.01	.01	10.	1.01	16.25	197	.31	.31	.00	579.
1.01	4.30	54	.01	0.01	.01	10.	1.01	16.30	198	.31	.31	.00	559.
1.01	4.35	55	.01	0.01	.01	10.	1.01	16.35	199	.31	.31	.00	548.
1.01	4.40	56	.01	0.01	.01	10.	1.01	16.40	200	.31	.31	.00	543.
1.01	4.45	57	.01	0.01	.01	11.	1.01	16.45	201	.31	.31	.00	541.
1.01	4.50	58	.01	0.01	.01	11.	1.01	16.50	202	.31	.31	.00	540.
1.01	4.55	59	.01	0.01	.01	11.	1.01	16.55	203	.31	.31	.00	540.
1.01	5.00	60	.01	0.01	.01	11.	1.01	17.00	204	.31	.31	.00	540.

1.01	5.05	61	.01	.01	.01	11.	1.01	17.05	205	.24	.24	.00	530.
1.01	5.10	62	.01	.01	.01	12.	1.01	17.10	206	.24	.24	.00	498.
1.01	5.15	63	.01	.01	.01	12.	1.01	17.15	207	.24	.24	.00	466.
1.01	5.20	64	.01	.01	.01	12.	1.01	17.20	208	.24	.24	.00	446.
1.01	5.25	65	.01	.01	.01	12.	1.01	17.25	209	.24	.24	.00	436.
1.01	5.30	66	.01	.01	.01	12.	1.01	17.30	210	.24	.24	.00	430.
1.01	5.35	67	.01	.01	.01	12.	1.01	17.35	211	.24	.24	.00	427.
1.01	5.40	68	.01	.01	.01	12.	1.01	17.40	212	.24	.24	.00	426.
1.01	5.45	69	.01	.01	.01	13.	1.01	17.45	213	.24	.24	.00	425.
1.01	5.50	70	.01	.01	.01	13.	1.01	17.50	214	.24	.24	.00	425.
1.01	5.55	71	.01	.01	.01	13.	1.01	17.55	215	.24	.24	.00	424.
1.01	6.00	72	.01	.01	.01	13.	1.01	18.00	216	.24	.24	.00	424.
1.01	6.05	73	.07	.04	.03	18.	1.01	18.05	217	.02	.02	.00	389.
1.01	6.10	74	.07	.04	.03	35.	1.01	18.10	218	.02	.02	.00	284.
1.01	6.15	75	.07	.05	.02	52.	1.01	18.15	219	.02	.02	.00	175.
1.01	6.20	76	.07	.05	.02	65.	1.01	18.20	220	.02	.02	.00	106.
1.01	6.25	77	.07	.05	.02	72.	1.01	18.25	221	.02	.02	.00	72.
1.01	6.30	78	.07	.05	.02	77.	1.01	18.30	222	.02	.02	.00	54.
1.01	6.35	79	.07	.05	.02	81.	1.01	18.35	223	.02	.02	.00	44.
1.01	6.40	80	.07	.05	.02	84.	1.01	18.40	224	.02	.02	.00	39.
1.01	6.45	81	.07	.05	.02	86.	1.01	18.45	225	.02	.02	.00	37.
1.01	6.50	82	.07	.05	.02	88.	1.01	18.50	226	.02	.02	.00	35.
1.01	6.55	83	.07	.05	.01	90.	1.01	18.55	227	.02	.02	.00	34.
1.01	7.00	84	.07	.05	.01	92.	1.01	19.00	228	.02	.02	.00	34.
1.01	7.05	85	.07	.06	.01	93.	1.01	19.05	229	.02	.02	.00	34.
1.01	7.10	86	.07	.06	.01	95.	1.01	19.10	230	.02	.02	.00	34.
1.01	7.15	87	.07	.06	.01	96.	1.01	19.15	231	.02	.02	.00	34.
1.01	7.20	88	.07	.06	.01	97.	1.01	19.20	232	.02	.02	.00	34.
1.01	7.25	89	.07	.06	.01	98.	1.01	19.25	233	.02	.02	.00	34.
1.01	7.30	90	.07	.06	.01	99.	1.01	19.30	234	.02	.02	.00	34.
1.01	7.35	91	.07	.06	.01	100.	1.01	19.35	235	.02	.02	.00	34.
1.01	7.40	92	.07	.06	.01	101.	1.01	19.40	236	.02	.02	.00	34.
1.01	7.45	93	.07	.06	.01	102.	1.01	19.45	237	.02	.02	.00	34.
1.01	7.50	94	.07	.06	.01	103.	1.01	19.50	238	.02	.02	.00	34.
1.01	7.55	95	.07	.06	.01	103.	1.01	19.55	239	.02	.02	.00	34.
1.01	8.00	96	.07	.06	.01	104.	1.01	20.00	240	.02	.02	.00	34.
1.01	8.05	97	.07	.06	.01	105.	1.01	20.05	241	.02	.02	.00	34.
1.01	8.10	98	.07	.06	.01	105.	1.01	20.10	242	.02	.02	.00	34.
1.01	8.15	99	.07	.06	.01	106.	1.01	20.15	243	.02	.02	.00	34.
1.01	8.20	100	.07	.06	.01	106.	1.01	20.20	244	.02	.02	.00	34.
1.01	8.25	101	.07	.06	.01	107.	1.01	20.25	245	.02	.02	.00	34.
1.01	8.30	102	.07	.06	.01	107.	1.01	20.30	246	.02	.02	.00	34.
1.01	8.35	103	.07	.06	.01	108.	1.01	20.35	247	.02	.02	.00	34.
1.01	8.40	104	.07	.06	.01	108.	1.01	20.40	248	.02	.02	.00	34.
1.01	8.45	105	.07	.06	.01	109.	1.01	20.45	249	.02	.02	.00	34.
1.01	8.50	106	.07	.06	.01	109.	1.01	20.50	250	.02	.02	.00	34.
1.01	8.55	107	.07	.06	.01	109.	1.01	20.55	251	.02	.02	.00	34.
1.01	9.00	108	.07	.06	.01	110.	1.01	21.00	252	.02	.02	.00	34.
1.01	9.05	109	.07	.06	.01	110.	1.01	21.05	253	.02	.02	.00	34.
1.01	9.10	110	.07	.06	.01	110.	1.01	21.10	254	.02	.02	.00	34.
1.01	9.15	111	.07	.06	.01	111.	1.01	21.15	255	.02	.02	.00	34.
1.01	9.20	112	.07	.06	.00	111.	1.01	21.20	256	.02	.02	.00	34.
1.01	9.25	113	.07	.06	.00	111.	1.01	21.25	257	.02	.02	.00	34.
1.01	9.30	114	.07	.06	.00	111.	1.01	21.30	258	.02	.02	.00	34.
1.01	9.35	115	.07	.06	.00	112.	1.01	21.35	259	.02	.02	.00	34.
1.01	9.40	116	.07	.06	.00	112.	1.01	21.40	260	.02	.02	.00	34.
1.01	9.45	117	.07	.06	.00	112.	1.01	21.45	261	.02	.02	.00	34.
1.01	9.50	118	.07	.06	.00	112.	1.01	21.50	262	.02	.02	.00	34.
1.01	9.55	119	.07	.06	.00	113.	1.01	21.55	263	.02	.02	.00	34.
1.01	10.00	120	.07	.06	.00	113.	1.01	22.00	264	.02	.02	.00	34.
1.01	10.05	121	.07	.07	.00	113.	1.01	22.05	265	.02	.02	.00	34.
1.01	10.10	122	.07	.07	.00	113.	1.01	22.10	266	.02	.02	.00	34.

1.01	10.15	123	.07	.07	.00	113.	1.01	22.15	267	.02	.02	.00	34.
1.01	10.20	124	.07	.07	.00	113.	1.01	22.20	268	.02	.02	.00	34.
1.01	10.24	125	.07	.07	.00	114.	1.01	22.25	269	.02	.02	.00	34.
1.01	10.30	126	.07	.07	.00	114.	1.01	22.30	270	.02	.02	.00	34.
1.01	10.35	127	.07	.07	.00	114.	1.01	22.35	271	.02	.02	.00	34.
1.01	10.40	128	.07	.07	.00	114.	1.01	22.40	272	.02	.02	.00	34.
1.01	10.45	129	.07	.07	.00	114.	1.01	22.45	273	.02	.02	.00	34.
1.01	10.50	130	.07	.07	.00	114.	1.01	22.50	274	.02	.02	.00	34.
1.01	10.55	131	.07	.07	.00	114.	1.01	22.55	275	.02	.02	.00	34.
1.01	11.00	132	.07	.07	.00	115.	1.01	23.00	276	.02	.02	.00	34.
1.01	11.05	133	.07	.07	.00	115.	1.01	23.05	277	.02	.02	.00	34.
1.01	11.10	134	.07	.07	.00	115.	1.01	23.10	278	.02	.02	.00	34.
1.01	11.15	135	.07	.07	.00	115.	1.01	23.15	279	.02	.02	.00	34.
1.01	11.20	136	.07	.07	.00	115.	1.01	23.20	280	.02	.02	.00	34.
1.01	11.25	137	.07	.07	.00	115.	1.01	23.25	281	.02	.02	.00	34.
1.01	11.30	138	.07	.07	.00	115.	1.01	23.30	282	.02	.02	.00	34.
1.01	11.35	139	.07	.07	.00	115.	1.01	23.35	283	.02	.02	.00	34.
1.01	11.40	140	.07	.07	.00	115.	1.01	23.40	284	.02	.02	.00	34.
1.01	11.45	141	.07	.07	.00	116.	1.01	23.45	285	.02	.02	.00	34.
1.01	11.50	142	.07	.07	.00	116.	1.01	23.50	286	.02	.02	.00	34.
1.01	11.55	143	.07	.07	.00	116.	1.01	23.55	287	.02	.02	.00	34.
1.01	12.00	144	.07	.07	.00	116.	1.02	0.00	288	.02	.02	.00	34.

SUM 33.93 32.49 1.44 56499.  
( 862.1)( 825.1)( 37.1)( 1599.87)

HYDROGRAPH AT STA000001 FOR PLAN 1, RTIO 1									
CES	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME				
INCHES	2716.	634.	196.	196.	56987.				
CMS	77.	10.	6.	6.	1600.				
THOUS CU M		26.20	32.44	32.44	32.44				
AC-FT		665.59	823.87	823.87	823.87				
		314.	389.	389.	389.				
		388.	480.	480.	480.				

# HYDROGRAPH AT STA000001 FOR PLAN 1, RTIO 1

HYDROGRAPH AT STA000001 FOR PLAN 1, RTIO 2									
CES	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME				
INCHES	136.	32.	10.	10.	2824.				
CMS	4.	1.	0.	0.	80.				
THOUS CU M		1.31	1.62	1.62	1.62				
AC-FT		33.28	41.19	41.19	41.19				
		16.	19.	19.	19.				
		19.	24.	24.	24.				

# HYDROGRAPH AT STA000001 FOR PLAN 1, RTIO 3

HYDROGRAPH AT STA000001 FOR PLAN 1, RTIO 3									
CES	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME				
INCHES	272.	63.	20.	20.	5849.				
CMS	6.	2.	1.	1.	160.				
THOUS CU M		2.62	3.24	3.24	3.24				
AC-FT		66.56	82.39	82.39	82.39				
		31.	39.	39.	39.				
		39.	48.	48.	48.				



PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
407.	95.	29.	29.	8473.
12.	3.	1.	1.	240.
CFS				
CMS				
INCHES				
	3.93	4.87	4.87	4.87
MM				
	99.84	123.58	123.58	123.58
AC-FT				
	47.	58.	58.	58.
THOUS CU M				
	58.	72.	72.	72.

HYDROGRAPH AT STA000001 FOR PLAN 1, RTIO 4

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
543.	127.	39.	39.	11297.
15.	4.	1.	1.	320.
CFS				
CMS				
INCHES				
	5.24	6.49	6.49	6.49
MM				
	133.12	164.77	164.77	164.77
AC-FT				
	63.	78.	78.	78.
THOUS CU M				
	78.	96.	96.	96.

HYDROGRAPH AT STA000001 FOR PLAN 1, RTIO 5

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
679.	158.	49.	49.	14122.
19.	4.	1.	1.	400.
CFS				
CMS				
INCHES				
	6.55	8.11	8.11	8.11
MM				
	166.40	205.97	205.97	205.97
AC-FT				
	79.	97.	97.	97.
THOUS CU M				
	97.	120.	120.	120.

HYDROGRAPH AT STA000001 FOR PLAN 1, RTIO 6

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
951.	222.	69.	69.	19771.
27.	6.	2.	2.	560.
CFS				
CMS				
INCHES				
	9.17	11.35	11.35	11.35
MM				
	232.96	288.36	288.36	288.36
AC-FT				
	110.	136.	136.	136.
THOUS CU M				
	136.	168.	168.	168.

HYDROGRAPH AT STA000001 FOR PLAN 1, RTIO 7

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
1358.	317.	98.	98.	28244.
38.	9.	3.	3.	800.
CFS				
CMS				
INCHES				
	13.10	16.22	16.22	16.22
MM				
	332.80	411.94	411.94	411.94
AC-FT				
	157.	195.	195.	195.
THOUS CU M				
	194.	240.	240.	240.

HYDROGRAPH AT STA000001 FOR PLAN 1, RTIO 8

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
2716.	634.	196.	196.	56487.
CFS				

CMS 77. 18. 6. 6. 1600.  
 INCHES 26.20 32.44 32.44 32.44  
 MM 665.59 823.87 823.87 823.87  
 AC-FT 314. 389. 389. 480.  
 THOUS CU M 388. 480. 480. 480.

\*\*\*\*\*

HYDROGRAPH ROUTING

ROUTED FLOWS THRU WELSHMANS LAKE DAM


	ROUTING DATA									
	ISTAQ	ICOMP	IECON	ITAPE	JPLT	JPRY	INAME	ISTAGE	IAUTO	
	000002	1	0	0	2	0	1	0	0	
	ROUTING DATA									
	GLSS	CLOSS	AVG	IRCS	ISAME	IOPT	IPMP	LSTR		
	0.0	0.000	0.00	1	1	0	0			
	NSTPS									
	NSTD	LAG	AMSKK	X	TSK	STORA	ISPRAT			
	1	0	0	0.000	0.000	-819.	-1			
STAGE	819.40	820.00	820.60	821.20	822.10	822.90	823.50	824.10	824.50	825.30
	826.10	826.80	827.10							
FLOW	0.00	20.00	50.00	100.00	200.00	300.00	400.00	500.00	600.00	800.00
	1000.00	1200.00	1300.00							
SURFACE AREA	0.	1.	2.	3.	5.	7.	10.	12.	15.	
CAPACITY	0.	1.	6.	18.	39.	70.	113.	167.	234.	
ELEVATION	794.	800.	805.	810.	815.	820.	825.	830.	835.	
CREL SPWID COOW EXPW ELEV COQL CAREA EXPL										
	819.4	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0

DAM DATA

	TOPEL	COOD	EXPD	DAMWID						
	823.9	2.0	1.5	420.						
CREST LENGTH	0.	27.	70.	120.	170.	200.	250.	405.	420.	445.
AT OR BELOW ELEVATION	823.9	824.0	824.7	824.9	824.9	825.3	825.3	825.6	825.7	827.0

STATION 000002 PLAN 1:1 RATIO 1

END-OF-PERIOD HYDROGRAPH ORIGINATES



STATION 000002, PLAN 1, RATIO 7

1/2 PMF

# END-OF-PERIOD HYDROGRAPH ORDINATES

OUTFLOW									
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
1.	0.	0.	0.	1.	1.	1.	1.	1.	1.
1.	1.	1.	1.	1.	1.	1.	1.	2.	2.
2.	2.	2.	2.	2.	2.	2.	2.	3.	3.
3.	3.	3.	3.	3.	3.	3.	3.	4.	4.
4.	4.	4.	4.	5.	6.	6.	7.	8.	9.
10.	11.	13.	14.	15.	16.	17.	17.	18.	19.
20.	22.	23.	24.	26.	27.	28.	27.	30.	31.
32.	33.	34.	35.	36.	37.	37.	38.	39.	40.
40.	41.	42.	42.	43.	43.	44.	45.	45.	46.
46.	47.	47.	47.	48.	48.	49.	49.	49.	50.
50.	50.	51.	51.	52.	52.	53.	53.	53.	54.
54.	54.	54.	55.	55.	58.	62.	69.	76.	83.
90.	97.	104.	112.	119.	126.	132.	138.	144.	151.
163.	169.	174.	174.	179.	184.	188.	191.	195.	199.
205.	211.	218.	224.	230.	236.	241.	245.	249.	253.
257.	257.	263.	263.	272.	272.	347.	445.	604.	774.
795.	799.	728.	652.	582.	524.	486.	461.	439.	419.
805.	371.	359.	348.	336.	325.	313.	301.	293.	293.
279.	272.	267.	261.	257.	251.	243.	231.	215.	215.
184.	170.	156.	144.	132.	122.	112.	104.	97.	97.
91.	86.	81.	76.	72.	68.	65.	61.	58.	55.
52.	50.	48.	47.	46.	44.	43.	42.	41.	40.
37.	38.	37.	36.	35.	34.	34.	33.	32.	32.
31.	30.	30.	29.	29.	28.	28.	27.	27.	26.
25.	25.	25.	24.	24.	24.	24.	23.	23.	23.
22.	22.	22.	22.	22.	21.	21.	21.	21.	21.

[illegible]

75. 75. 75. 74. 74. 74. 74. 73.  
 73. 73. 73. 73. 72. 72. 72. 72.  
 72. 72. 72. 72. 71. 71. 71. 71.  
 71. 71. 71. 71. 71. 71. 71. 71.

STAGE

819.4	819.4	819.4	819.4	819.4	819.4	819.4	819.4	819.4	819.4	819.4	819.4	819.4
819.4	819.4	819.4	819.4	819.4	819.4	819.4	819.4	819.4	819.4	819.4	819.4	819.4
819.4	819.4	819.4	819.4	819.4	819.4	819.4	819.4	819.4	819.4	819.4	819.4	819.4
819.4	819.4	819.4	819.4	819.4	819.4	819.4	819.4	819.4	819.4	819.4	819.4	819.4
819.5	819.5	819.5	819.5	819.5	819.5	819.5	819.5	819.5	819.5	819.5	819.5	819.5
819.5	819.5	819.5	819.5	819.5	819.5	819.5	819.5	819.5	819.5	819.5	819.5	819.5
819.5	819.5	819.5	819.5	819.5	819.5	819.5	819.5	819.5	819.5	819.5	819.5	819.5
819.7	819.7	819.7	819.7	819.7	819.7	819.7	819.7	819.7	819.7	819.7	819.7	819.7
820.0	820.0	820.0	820.0	820.0	820.0	820.0	820.0	820.0	820.0	820.0	820.0	820.0
820.2	820.2	820.2	820.2	820.2	820.2	820.2	820.2	820.2	820.2	820.2	820.2	820.2
820.4	820.4	820.4	820.4	820.4	820.4	820.4	820.4	820.4	820.4	820.4	820.4	820.4
820.5	820.5	820.5	820.5	820.5	820.5	820.5	820.5	820.5	820.5	820.5	820.5	820.5
820.6	820.6	820.6	820.6	820.6	820.6	820.6	820.6	820.6	820.6	820.6	820.6	820.6
820.7	820.7	820.7	820.7	820.7	820.7	820.7	820.7	820.7	820.7	820.7	820.7	820.7
821.1	821.1	821.1	821.1	821.1	821.1	821.1	821.1	821.1	821.1	821.1	821.1	821.1
821.7	821.7	821.7	821.7	821.7	821.7	821.7	821.7	821.7	821.7	821.7	821.7	821.7
822.1	822.1	822.1	822.1	822.1	822.1	822.1	822.1	822.1	822.1	822.1	822.1	822.1
822.5	822.5	822.5	822.5	822.5	822.5	822.5	822.5	822.5	822.5	822.5	822.5	822.5
822.6	822.6	822.6	822.6	822.6	822.6	822.6	822.6	822.6	822.6	822.6	822.6	822.6
824.9	824.9	824.9	824.9	824.9	824.9	824.9	824.9	824.9	824.9	824.9	824.9	824.9
824.5	824.5	824.5	824.5	824.5	824.5	824.5	824.5	824.5	824.5	824.5	824.5	824.5
822.8	822.8	822.8	822.8	822.8	822.8	822.8	822.8	822.8	822.8	822.8	822.8	822.8
822.1	822.1	822.1	822.1	822.1	822.1	822.1	822.1	822.1	822.1	822.1	822.1	822.1
821.1	821.1	821.1	821.1	821.1	821.1	821.1	821.1	821.1	821.1	821.1	821.1	821.1
820.6	820.6	820.6	820.6	820.6	820.6	820.6	820.6	820.6	820.6	820.6	820.6	820.6
820.4	820.4	820.4	820.4	820.4	820.4	820.4	820.4	820.4	820.4	820.4	820.4	820.4
820.2	820.2	820.2	820.2	820.2	820.2	820.2	820.2	820.2	820.2	820.2	820.2	820.2
820.1	820.1	820.1	820.1	820.1	820.1	820.1	820.1	820.1	820.1	820.1	820.1	820.1
820.1	820.1	820.1	820.1	820.1	820.1	820.1	820.1	820.1	820.1	820.1	820.1	820.1

PEAK OUTFLOW IS 835. AT TIME 15.92 HOURS

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
835.	300.	96.	96.	27591.
24.	8.	3.	3.	781.
CFS				
CM	12.40	15.84	15.84	15.84
INCHES	314.95	402.41	402.41	402.41
MM	149.	190.	190.	190.
AC-FI	183.	234.	234.	234.
THOUS CU M				

0000

STATION0000002

	0.	200.	400.	600.	800.	1000.	1200.	1400.	0.	0.	0.	0.	0.	0.
0.														
0.05														
0.10														
0.15														
0.20														
0.25														
0.30														
0.35														
0.40														
0.45														
0.50														
0.55														
1.00														
1.05														
1.10														
1.15														
1.20														
1.25														
1.30														
1.35														
1.40														
1.45														
1.50														
1.55														
2.00														
2.05														
2.10														
2.15														
2.20														
2.25														
2.30														
2.35														
2.40														
2.45														
2.50														
2.55														
3.00														
3.05														
3.10														
3.15														
3.20														
3.25														
3.30														
3.35														
3.40														
3.45														
3.50														
3.55														
4.00														
4.05														
4.10														
4.15														
4.20														
4.25														
4.30														
4.35														
4.40														

PLATE D-15

PLATE D-16

PLATE D-17





20.15243.10  
 20.20244.10  
 20.25245.10  
 20.30246.10  
 20.35247.10  
 20.40248.10  
 20.45249.10  
 20.50250.10  
 20.55251.10  
 21.00252.10  
 21.05253.10  
 21.10254.10  
 21.15255.10  
 21.20256.10  
 21.25257.10  
 21.30258.10  
 21.35259.10  
 21.40260.10  
 21.45261.10  
 21.50262.10  
 21.55263.10  
 22.00264.10  
 22.05265.10  
 22.10266.10  
 22.15267.10  
 22.20268.10  
 22.25269.10  
 22.30270.10  
 22.35271.10  
 22.40272.10  
 22.45273.10  
 22.50274.10  
 22.55275.10  
 23.00276.10  
 23.05277.10  
 23.10278.10  
 23.15279.10  
 23.20280.10  
 23.25281.10  
 23.30282.10  
 23.35283.10  
 23.40284.10  
 23.45285.10  
 23.50286.10  
 23.55287.10  
 24.00288.10

STATION 000002, PLAN 1, RATIO 6

## END-OF-PERIOD HYDROGRAPH ORDINATES

[illegible]

STORAGE									
66.	66.	66.	66.	66.	66.	66.	66.	66.	66.
66.	66.	66.	66.	66.	66.	66.	66.	66.	66.
66.	66.	66.	66.	66.	66.	66.	66.	66.	66.
66.	66.	66.	66.	66.	66.	66.	66.	66.	66.
66.	66.	66.	66.	66.	66.	66.	66.	66.	66.
67.	67.	67.	67.	67.	67.	67.	67.	67.	67.
67.	67.	67.	67.	67.	67.	67.	67.	67.	67.
68.	68.	68.	68.	68.	68.	68.	68.	68.	68.
71.	71.	71.	72.	72.	73.	73.	73.	74.	74.
75.	75.	75.	76.	76.	76.	76.	77.	77.	77.
77.	78.	78.	78.	78.	78.	78.	79.	79.	79.
79.	79.	79.	79.	79.	79.	80.	80.	80.	80.
80.	80.	80.	80.	80.	80.	80.	80.	80.	80.
80.	80.	80.	80.	80.	80.	80.	80.	80.	80.
81.	81.	81.	81.	81.	81.	81.	81.	84.	86.
87.	88.	89.	90.	91.	92.	92.	93.	94.	95.
26.	26.	27.	28.	29.	29.	29.	29.	29.	29.
101.	101.	102.	103.	103.	104.	105.	105.	105.	105.
106.	106.	106.	106.	107.	107.	110.	114.	120.	124.
121.	119.	117.	115.	113.	112.	110.	109.	108.	108.
107.	107.	106.	106.	106.	106.	105.	105.	104.	104.
103.	103.	103.	102.	102.	102.	102.	101.	100.	98.
26.	94.	92.	91.	89.	88.	87.	86.	85.	84.
03.	82.	81.	80.	80.	80.	79.	79.	78.	78.



\*OVF\*

STATION000002

	0.	400.	800.	1200.	1600.	2000.	2400.	2800.	0.	0.	0.	0.	0.
.05 11	.	.	.	.	.	.	.	.	.	.	.	.	.
.10 21	.	.	.	.	.	.	.	.	.	.	.	.	.
.15 31	.	.	.	.	.	.	.	.	.	.	.	.	.
.20 41	.	.	.	.	.	.	.	.	.	.	.	.	.
.25 51	.	.	.	.	.	.	.	.	.	.	.	.	.
.30 61	.	.	.	.	.	.	.	.	.	.	.	.	.
.35 71	.	.	.	.	.	.	.	.	.	.	.	.	.
.40 81	.	.	.	.	.	.	.	.	.	.	.	.	.
.45 91	.	.	.	.	.	.	.	.	.	.	.	.	.
.50 101	.	.	.	.	.	.	.	.	.	.	.	.	.
.55 111	.	.	.	.	.	.	.	.	.	.	.	.	.
1.00 121	.	.	.	.	.	.	.	.	.	.	.	.	.
1.05 131	.	.	.	.	.	.	.	.	.	.	.	.	.
1.10 141	.	.	.	.	.	.	.	.	.	.	.	.	.
1.15 151	.	.	.	.	.	.	.	.	.	.	.	.	.
1.20 161	.	.	.	.	.	.	.	.	.	.	.	.	.
1.25 171	.	.	.	.	.	.	.	.	.	.	.	.	.
1.30 181	.	.	.	.	.	.	.	.	.	.	.	.	.
1.35 191	.	.	.	.	.	.	.	.	.	.	.	.	.
1.40 201	.	.	.	.	.	.	.	.	.	.	.	.	.
1.45 211	.	.	.	.	.	.	.	.	.	.	.	.	.
1.50 221	.	.	.	.	.	.	.	.	.	.	.	.	.
1.55 231	.	.	.	.	.	.	.	.	.	.	.	.	.
2.00 241	.	.	.	.	.	.	.	.	.	.	.	.	.
2.05 251	.	.	.	.	.	.	.	.	.	.	.	.	.
2.10 261	.	.	.	.	.	.	.	.	.	.	.	.	.
2.15 271	.	.	.	.	.	.	.	.	.	.	.	.	.
2.20 281	.	.	.	.	.	.	.	.	.	.	.	.	.
2.25 291	.	.	.	.	.	.	.	.	.	.	.	.	.
2.30 301	.	.	.	.	.	.	.	.	.	.	.	.	.
2.35 311	.	.	.	.	.	.	.	.	.	.	.	.	.
2.40 321	.	.	.	.	.	.	.	.	.	.	.	.	.
2.45 331	.	.	.	.	.	.	.	.	.	.	.	.	.
2.50 341	.	.	.	.	.	.	.	.	.	.	.	.	.
2.55 351	.	.	.	.	.	.	.	.	.	.	.	.	.
3.00 361	.	.	.	.	.	.	.	.	.	.	.	.	.
3.05 371	.	.	.	.	.	.	.	.	.	.	.	.	.
3.10 381	.	.	.	.	.	.	.	.	.	.	.	.	.
3.15 391	.	.	.	.	.	.	.	.	.	.	.	.	.
3.20 401	.	.	.	.	.	.	.	.	.	.	.	.	.
3.25 411	.	.	.	.	.	.	.	.	.	.	.	.	.
3.30 421	.	.	.	.	.	.	.	.	.	.	.	.	.
3.35 431	.	.	.	.	.	.	.	.	.	.	.	.	.
3.40 441	.	.	.	.	.	.	.	.	.	.	.	.	.
3.45 451	.	.	.	.	.	.	.	.	.	.	.	.	.
3.50 461	.	.	.	.	.	.	.	.	.	.	.	.	.
3.55 471	.	.	.	.	.	.	.	.	.	.	.	.	.
4.00 481	.	.	.	.	.	.	.	.	.	.	.	.	.
4.05 491	.	.	.	.	.	.	.	.	.	.	.	.	.
4.10 501	.	.	.	.	.	.	.	.	.	.	.	.	.
4.15 511	.	.	.	.	.	.	.	.	.	.	.	.	.
4.20 521	.	.	.	.	.	.	.	.	.	.	.	.	.
4.25 531	.	.	.	.	.	.	.	.	.	.	.	.	.
4.30 541	.	.	.	.	.	.	.	.	.	.	.	.	.
4.35 551	.	.	.	.	.	.	.	.	.	.	.	.	.
4.40 561	.	.	.	.	.	.	.	.	.	.	.	.	.

PLATE D-22







20.15243.10  
20.20244.10  
20.25245.10  
20.30246.10  
20.35247.10  
20.40248.10  
20.45249.10  
20.50250.1  
20.55251.1  
21.00252.1  
21.05253.1  
21.10254.1  
21.15255.1  
21.20256.1  
21.25257.1  
21.30258.1  
21.35259.1  
21.40260.1  
21.45261.1  
21.50262.1  
21.55263.1  
22.00264.1  
22.05265.1  
22.10266.1  
22.15267.1  
22.20268.1  
22.25269.1  
22.30270.1  
22.35271.1  
22.40272.1  
22.45273.1  
22.50274.1  
22.55275.1  
23.00276.1  
23.05277.1  
23.10278.1  
23.15279.1  
23.20280.1  
23.25281.1  
23.30282.1  
23.35283.1  
23.40284.1  
23.45285.1  
23.50286.1  
23.55287.1  
0.00288.1



PLAK FLOW AND STORAGE (END OF PERIOD) SUMMARY FOR MULTIPLE PLAN-RATIO ECONOMIC COMPUTATIONS  
 FLOWS IN CUBIC FEET PER SECOND (CUBIC METERS PER SECOND)  
 AREA IN SQUARE MILES (SQUARE KILOMETERS)

OPERATION	STATION	AREA	PLAN	RATIOS APPLIED TO FLOWS							
				RATIO 1	RATIO 2	RATIO 3	RATIO 4	RATIO 5	RATIO 6	RATIO 7	RATIO 8
				.05	.10	.15	.20	.25	.35	.50	1.00
HYDROGRAPH AT	000001	.23 (.50)	1	136. ( 3.85)	272. ( 7.69)	407. (11.54)	543. (15.38)	679. (19.23)	951. (26.92)	1358. (38.46)	2716. (76.92)
	ROUTED TO	.23 (.50)	1	41. ( 1.16)	102. ( 2.89)	173. ( 4.90)	241. ( 6.83)	309. ( 8.74)	462. (13.08)	835. (23.65)	2541. (71.95)

# SUMMARY OF DAM SAFETY ANALYSIS

PLAN 1 ..... INITIAL VALUE ..... SPILLWAY CREST ..... TOP OF DAM  
 ELEVATION 819.40 ..... 819.40 ..... 823.90  
 STORAGE 66 ..... 66 ..... 102  
 OUTFLOW 0 ..... 0 ..... 467

RATIO OF PMF	MAXIMUM RESERVOIR W.S.ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
.05	820.42	0.00	74.	41.	0.00	16.17	0.00
.10	821.22	0.00	80.	102.	0.00	16.08	0.00
.15	821.86	0.00	85.	173.	0.00	16.00	0.00
.20	822.43	0.00	90.	241.	0.00	16.00	0.00
.25	822.93	0.00	94.	309.	0.00	16.00	0.00
.35	823.87	0.00	102.	462.	0.00	16.00	0.00
.50	824.90	1.00	112.	835.	.75	15.92	0.00
1.00	826.13	2.23	124.	2541.	3.33	15.75	0.00

APPENDIX E  
GEOLOGY REPORT

ENGINEERING GEOLOGY OF THE PAUL J. WILLIAMS LAKE SITE, ST. FRANCOIS COUNTY

The proposed Paul Williams lake site located in the SE $\frac{1}{4}$  SW $\frac{1}{4}$  sec. 15, T.37 N., R.4 E. (Bonne Terre Quad.) is geologically feasible. If the following recommendations based on geological conditions are followed little or no trouble is anticipated.

Geologically this site is located in the Derby-Doerun Formation which consists of thin bedded limestone, silts, and shales. The soil cover varies in thickness but seldom will be found over 10 feet in thickness. This soil will be quite adequate for embankment material if the material is placed in lifts and compacted to its maximum density. Although most of the stone was covered at the dam site there are indications that alternating beds of thin limestones and shales will be encountered which will cause little difficulty in constructing an adequate core trench. However, it is very important that all loose limestone blocks be removed down to fresh solid rock. The loose material should be removed off the silt and shale horizons. If the core is not cut into fresh solid limestone rock especially on the abutments then there will be a possibility of leakage through bedding planes of the thin bedded limestone along the bedding planes. The use of powder should be kept at a minimum and could possibly be used to insure good trenches on the abutments but probably should not be used on the floor of the valley. The core trench in the flood of the valley should be cut to fresh rock and the limestone slabs that can be broken and pulled out with a back mounted ripper on the large cat should be sufficient.

The material from the core trench can be put off to one side and incorporated as part of the downstream portion of the embankment. Due to the alternating beds of limestone and shale it is recommended that a blanket of natural soil be left for approximately 50 to 75 feet upstream from the toe of the dam. This will aid in restricting the flow of water underneath the embankment material.

*Edwin E. Lutzen*

Edwin E. Lutzen  
Engineering Geologist  
Missouri Geological Survey  
April 29, 1969

END

DATE  
FILMED

11-81

DTIC